

Attachment D

Line 5 Wisconsin Segment Relocation Project
Waterbodies Crossed or Affected by the Project Facilities

Milepost	Feature Unique ID Number	Map Page Number	Flow Regime	Waterbody USGS	County	Feature Description	Crossing ^a Width	OHWM ^b Width	Bank Width ^c	Location	OR/WRW ^d	Agency Classification	Time-of-Year Restriction	Navigability Determination Requested	Latitude	Longitude	Proposed Crossing Method ^e	Bridge Type ^f	Bridge ^g	Dredging	Grading
N/A	WDH-01	2	Intermittent	UNT of South Fish Creek	Bayfield	WDH Waterbody	N/A	TBD	TBD	RSV1 Valve Site ATWS ^b			Mar 1 - Jun 15		46.56149027	-90.98098939	N/A	N/A	N	N	N
0.6	sa0009	3	Perennial	Bay City Creek	Ashland	Natural	16	12	14	Construction ROW			Mar 1 - Jun 15		46.55099028	-90.8945767	DC	Timber Mat	Y	Y	Y
1.5	WDH-02	5	Intermittent	UNT of Little Beartrap Creek	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15		46.53813544	-90.89526847	OC/DC	Timber Mat	Y	Y	Y
1.5	WDH-03	5	Intermittent	UNT of Little Beartrap Creek	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15		46.53747186	-90.89526407	OC/DC	Timber Mat	Y	Y	Y
1.8	WDH-04	5	Intermittent	UNT of Little Beartrap Creek	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15		46.53281954	-90.8957127	OC/DC	Timber Mat	Y	Y	Y
2.2	sa00471	6	Intermittent	Little Beartrap Creek	Ashland	Natural	11	6	9	Construction ROW			Mar 1 - Jun 15		46.5280072	-90.89515063	OC/DC	Timber Mat	Y	Y	Y
2.2	sa00466	6	Epheermal	UNT of Little Beartrap Creek	Ashland	Manipulated	6	4	6	Construction ROW			Mar 1 - Jun 15		46.5274827	-90.89512631	OC/DC	Timber Mat	Y	Y	Y
2.6	WDH-100	6	Intermittent	UNT of Little Beartrap Creek	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15	Yes	46.52167006	-90.89513742	OC/DC	Timber Mat	Y	Y	Y
2.9	sa00071	6	Intermittent	Beartrap Creek	Ashland	Natural	7	6	10	Construction ROW	ORW	ASNRI-PNW	Mar 1 - Jun 15		46.51819027	-90.89504548	OC/DC	Timber Mat	Y	Y	Y
3.8	sa0011e_ext	8	Intermittent	UNT of White River	Ashland	Natural	2	1	1	Construction ROW			Mar 1 - Jun 15		46.50544507	-90.89470392	HDD	Timber Mat	Y	Y	Y
3.8	sa0022	8	Intermittent	UNT of White River	Ashland	Natural	4	4	40	Construction ROW			Mar 1 - Jun 15		46.50502591	-90.89462656	HDD	Timber Mat	Y	N	Y
3.9	WDH-05	8	Intermittent	UNT of White River	Ashland	WDH Waterbody	N/A	TBD	TBD	Access Road 201.02			Mar 1 - Jun 15		46.50318435	-90.89321412	N/A	Timber Mat	Y	N	Y
4.0	sa0024	8	Epheermal	UNT of White River	Ashland	Natural	2	2	3	Construction ROW			Mar 1 - Jun 15		46.50226341	-90.89463333	HDD	Timber Mat	Y	N	Y
4.0	sa0023	8	Perennial	White River	Ashland	Natural	TBD	TBD	TBD	Construction ROW	ERW	Class II Trout, ASNRI-PNW	Sep 15 - May 15		46.50221412	-90.89472167	HDD	Rail Car	Y	N	Y
4.7	sa00131	9	Intermittent	UNT of White River	Ashland	Natural	3	3	11	Construction ROW			Mar 1 - Jun 15		46.49377331	-90.8974119	OC/DC	Timber Mat	Y	Y	Y
4.7	sa00146	9	Epheermal	UNT of White River	Ashland	Natural	N/A	2	10	Construction ROW			Mar 1 - Jun 15		46.49384459	-90.89762175	OC/DC	Timber Mat	Y	Y	Y
4.8	WDH-06	9	Intermittent	UNT of White River	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15		46.49331746	-90.90028968	OC/DC	Timber Mat	Y	Y	Y
5.0	sa0041p	9	Perennial	Rock Creek	Ashland	Natural	5	10	30	Construction ROW			Mar 1 - Jun 15		46.49068062	-90.90075438	DC	Timber Mat	Y	Y	Y
5.5	sa00166	9	Epheermal	UNT of Rock Creek	Ashland	Artificial/Man-made	2	2	3	Construction ROW			Mar 1 - Jun 15		46.48641297	-90.90605039	OC/DC	Timber Mat	Y	Y	Y
5.5	sa00366	9	Epheermal	UNT of Rock Creek	Ashland	Artificial/Man-made	2	2	5	Construction ROW			Mar 1 - Jun 15		46.48586387	-90.90574086	OC/DC	Timber Mat	Y	Y	Y
5.8	sa00376	10	Epheermal	UNT of Deer Creek	Ashland	Natural	3	2	10	Construction ROW			Mar 1 - Jun 15		46.48254568	-90.90371638	OC/DC	Timber Mat	Y	Y	Y
5.8	sa00386	10	Epheermal	UNT of Deer Creek	Ashland	Natural	3	2	7	Construction ROW			Mar 1 - Jun 15		46.48214041	-90.90345971	OC/DC	Timber Mat	Y	Y	Y
5.9	sa0039i_x1	10	Intermittent	UNT of Deer Creek	Ashland	Natural	16	12	30	Construction ROW			Mar 1 - Jun 15		46.48071032	-90.90261396	OC/DC	Timber Mat	Y	Y	Y
5.9	sa0039i_x2	10	Intermittent	UNT of Deer Creek	Ashland	Natural	5	12	30	Construction ROW			Mar 1 - Jun 15		46.48064063	-90.90257123	OC/DC	Timber Mat	Y	Y	Y
5.9	sa0040e	10	Epheermal	UNT of Deer Creek	Ashland	Natural	N/A	10	10	Construction ROW			Mar 1 - Jun 15		46.48047244	-90.90255186	OC/DC	Timber Mat	Y	Y	Y
5.9	WDH-07	10	Intermittent	UNT of Deer Creek	Ashland	WDH Waterbody	N/A	TBD	TBD	Access Road 013			Mar 1 - Jun 15		46.47913586	-90.9058236	N/A	Timber Mat	Y	N	Y
6.3	sa0027p	10	Perennial	Deer Creek	Ashland	Natural	30	25	30	Construction ROW			Mar 1 - Jun 15		46.47490468	-90.89959773	DC	Rail Car	Y	Y	Y
6.3	sa0028p	10	Epheermal	UNT of Deer Creek	Ashland	Natural	3	2	7	Construction ROW			Mar 1 - Jun 15		46.47438043	-90.89918193	OC/DC	Timber Mat	Y	Y	Y
6.4	sa0021e	10	Epheermal	UNT of Deer Creek	Ashland	Natural	1	5	7	Construction ROW			Mar 1 - Jun 15		46.47440433	-90.89938265	OC/DC	Timber Mat	Y	Y	Y
6.6	sa0067e	11	Epheermal	UNT of Deer Creek	Ashland	Natural	3	2	4	Construction ROW			Mar 1 - Jun 15		46.47075456	-90.89878806	OC/DC	Timber Mat	Y	Y	Y
6.9	WDH-101	11	Intermittent	UNT of Deer Creek	Ashland	WDH Waterbody	N/A	TBD	TBD	Access Road 014			Mar 1 - Jun 15	Yes	46.46647515	-90.9032054	N/A	Timber Mat	Y	N	Y
7.0	sa00661	11	Intermittent	UNT of Deer Creek	Ashland	Natural	11	8	10	Construction ROW			Mar 1 - Jun 15		46.46474712	-90.89878992	OC/DC	Timber Mat	Y	Y	Y
7.1	sa0068e	11	Epheermal	UNT of Deer Creek	Ashland	Artificial/Man-made	3	1	4	Construction ROW			Mar 1 - Jun 15		46.46333381	-90.89878699	OC/DC	Timber Mat	Y	Y	Y
7.6	sa00151	12	Intermittent	UNT of Marengo River	Ashland	Natural	8	8	8	Construction ROW			Mar 1 - Jun 15		46.45704937	-90.89864055	OC/DC	Timber Mat	Y	Y	Y
7.8	sa00403_x1	12	Perennial	Pond	Ashland	Artificial/Man-made	N/A	N/A	N/A	Construction ROW			Mar 1 - Jun 15		46.45353674	-90.89884274	DC	Timber Mat	Y	Y	Y
7.8	sa00403_x2	12	Perennial	Pond	Ashland	Artificial/Man-made	N/A	N/A	N/A	Construction ROW			Mar 1 - Jun 15		46.45291524	-90.89884094	DC	Timber Mat	Y	Y	Y
8.0	sa0011p	12	Perennial	UNT of Marengo River	Ashland	Natural	10	9	15	Construction ROW			Sep 15 - May 15		46.45115632	-90.89863432	DC	Timber Mat	Y	Y	Y
8.0	sa00096	13	Epheermal	Ditch	Ashland	Artificial/Man-made	N/A	1	5	Access Road 016		perennial tributary of trout stream	Mar 1 - Jun 15		46.45019896	-90.90149125	N/A	Timber Mat	Y	N	Y
8.0	WDH-08	13	Intermittent	UNT of Marengo River	Ashland	WDH Waterbody	N/A	TBD	TBD	Access Road 016			Mar 1 - Jun 15		46.45016986	-90.90092977	N/A	Timber Mat	Y	N	Y
8.0	sa0012e_x1	13	Epheermal	Ditch	Ashland	Artificial/Man-made	N/A	1	5	Construction ROW			Mar 1 - Jun 15		46.45010871	-90.89865762	OC/DC	Timber Mat	Y	Y	Y
8.0	sa0012e_x2	13	Epheermal	Ditch	Ashland	Artificial/Man-made	N/A	1	5	Access Road 016			Mar 1 - Jun 15		46.45010308	-90.89863555	N/A	Timber Mat	Y	N	Y
8.6	sa0013e	13	Epheermal	Ditch	Ashland	Artificial/Man-made	3	3	6	Construction ROW			Mar 1 - Jun 15		46.44302278	-90.89431593	OC/DC	Timber Mat	Y	Y	Y
8.6	sa0021e	13	Epheermal	Ditch	Ashland	Artificial/Man-made	4	4	6	Construction ROW			Mar 1 - Jun 15		46.44283591	-90.89431065	OC/DC	Timber Mat	Y	Y	Y
8.8	sa00201	13	Intermittent	UNT of Marengo River	Ashland	Manipulated	N/A	6	10	Access Road 018			Mar 1 - Jun 15		46.44277214	-90.89003495	N/A	Timber Mat	Y	N	Y
8.8	WDH-102_x1	13	Intermittent	UNT of Marengo River	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW	ORW	Class III Trout, ASNRI-PNW	Mar 1 - Jun 15	Yes	46.44185851	-90.89176035	OC/DC	Timber Mat	Y	Y	Y
8.8	WDH-102_x2	13	Intermittent	UNT of Marengo River	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW	ORW	Class III Trout, ASNRI-PNW	Mar 1 - Jun 15	Yes	46.44157655	-90.89174009	OC/DC	Timber Mat	Y	Y	Y
8.8	WDH-102_x3	13	Intermittent	UNT of Marengo River	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15	Yes	46.44152971	-90.89162921	OC/DC	Timber Mat	Y	Y	Y
9.0	WDH-09_x1	14	Intermittent	UNT of Marengo River	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15		46.43965669	-90.88757591	OC/DC	Timber Mat	Y	Y	Y
9.1	WDH-09_x2	14	Intermittent	UNT of Marengo River	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15		46.43864619	-90.88591358	OC/DC	Timber Mat	Y	Y	Y
9.2	WDH-09_x3	14	Intermittent	UNT of Marengo River	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15		46.43745406	-90.88442533	OC/DC	Timber Mat	Y	Y	Y
11.1	WDH-10_x1	16	Intermittent	UNT of Marengo River	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15		46.43503166	-90.84886399	OC/DC	Timber Mat	Y	Y	Y
11.1	WDH-10_x2	16	Intermittent	UNT of Marengo River	Ashland	WDH Waterbody	N/A	TBD	TBD	Construction Road 021			Mar 1 - Jun 15		46.43169406	-90.84837184	N/A	Timber Mat	Y	N	Y
11.1	sa0023e	15	Epheermal	Ditch	Ashland	Artificial/Man-made	N/A	3	4	West Pipeway			Mar 1 - Jun 15		46.43993233	-90.84515045	N/A	Timber Mat	Y	N	Y
11.1	sa0024e	15	Epheermal	Ditch	Ashland	Artificial/Man-made	N/A	1	2	West Pipeway			Mar 1 - Jun 15		46.43963597	-90.84330866	N/A	Timber Mat	Y	N	Y
11.2	WDH-11_x1	16	Perennial	Marengo River	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW	ORW	Class III Trout, ASNRI-PNW	Sep 15 - May 15		46.42920214	-90.84737432	HDD	Rail Car	Y	N	Y
11.3	WDH-11_x2	16	Perennial	Marengo River	Ashland	WDH Waterbody	N/A	TBD	TBD	Access Road 021.01	ORW	Class III Trout, ASNRI-PNW	Sep 15 - May 15		46.42836153	-90.84729542	N/A	Rail Car	Y	N	Y
11.9	WDH-12	16	Intermittent	UNT of Marengo River	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15		46.42425933	-90.83704483	OC/DC	Timber Mat	Y	Y	Y
12.2	WDH-13_x1	17	Intermittent	UNT of Marengo River	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15		46.42244401	-90.83044272	OC/DC	Timber Mat	Y	Y	Y
12.3	WDH-13_x2	17	Intermittent	UNT of Marengo River	Ashland	WDH Waterbody	N/A	TBD	TBD	Access Road 023			Mar 1 - Jun 15		46.42187571	-90.83064081	N				

22.1	sasv019p	25	Perennial	Krause Creek	Ashland	Natural	15	15	25	Construction ROW	ERW	Class I Trout, ASNRI-PNW	Sep 15 - May 15	46.35188033	-90.68095467	DC	Timber Mat	Y	Y	Y
22.2	sas043i_x1	26	Intermittent	UNT of Krause Creek	Ashland	Natural	N/A	3	10	Access Road 050			Mar 1 - Jun 15	46.34350519	-90.67566498	N/A	Timber Mat	Y	N	Y
22.7	sas043i_x2	26	Intermittent	UNT of Krause Creek	Ashland	Natural	N/A	3	10	Access Road 050			Mar 1 - Jun 15	46.34360923	-90.67565401	N/A	Timber Mat	Y	N	Y
22.9	sas005e	26	Epheermal	UNT of Bad River	Ashland	Artificial/Man-made	N/A	1	2	Access Road 050.01			Mar 1 - Jun 15	46.34146491	-90.67392835	N/A	Timber Mat	Y	N	Y
23.0	sasb003e	26	Epheermal	Ditch	Ashland	Artificial/Man-made	N/A	2	3	Access Road 050.01			Mar 1 - Jun 15	46.34087763	-90.67223289	N/A	Timber Mat	Y	N	Y
23.3	sas069i_x1	27	Intermittent	UNT of Bad River	Ashland	Natural	6	4	7	Construction ROW			Mar 1 - Jun 15	46.33852842	-90.66670703	OC/DC	Timber Mat	Y	Y	Y
23.3	sas069i_x2	27	Intermittent	UNT of Bad River	Ashland	Natural	12	4	7	Construction ROW			Mar 1 - Jun 15	46.33848463	-90.66649302	OC/DC	Timber Mat	Y	Y	Y
23.4	sas069i_x3	27	Intermittent	UNT of Bad River	Ashland	Natural	7	4	7	Construction ROW			Mar 1 - Jun 15	46.33808223	-90.66551326	OC/DC	Timber Mat	Y	Y	Y
23.4	sas069i_x4	27	Intermittent	UNT of Bad River	Ashland	Natural	5	4	7	Construction ROW			Mar 1 - Jun 15	46.33793735	-90.66518868	OC/DC	Timber Mat	Y	Y	Y
23.5	sas009p	27	Perennial	UNT of Bad River	Ashland	Natural	5	5	7	Construction ROW			Sep 15 - May 15	46.33688291	-90.6627645	DC	Rail Car	Y	N	Y
23.6	WDH-29	27	Perennial	UNT of Bad River	Ashland	WDH Waterbody	N/A	TBD	TBD	Access Road 050.02		<i>perennial tributary of trout stream</i>	Sep 15 - May 15	46.33412897	-90.66433473	N/A	Timber Mat	Y	N	Y
24.0	sasb006p	27	Perennial	Bad River	Ashland	Natural	70	60	60	Construction ROW	ERW	Class III Trout, ASNRI-PNW	Sep 15 - May 15	46.33579907	-90.653778	HDD	Rail Car	Y	N	Y
26.5	sasv010i	29	Intermittent	UNT of Scott Taylor Creek	Ashland	Natural	5	4.5	6	Construction ROW			Mar 1 - Jun 15	46.34916626	-90.61094042	OC/DC	Timber Mat	Y	Y	Y
26.9	sasv008i	29	Intermittent	UNT of Scott Taylor Creek	Ashland	Natural	3	3	6	Construction ROW			Mar 1 - Jun 15	46.3321287	-90.60363719	OC/DC	Timber Mat	Y	Y	Y
27.0	sasv011e	29	Epheermal	UNT of Scott Taylor Creek	Ashland	Natural	N/A	1	3	Construction ROW			Mar 1 - Jun 15	46.33583355	-90.60214779	OC/DC	Timber Mat	Y	Y	Y
27.2	WDH-50	29	Intermittent	UNT of Scott Taylor Creek	Ashland	WDH Waterbody	TBD	TBD	TBD	Construction ROW			Mar 1 - Jun 15	46.35588393	-90.60246477	OC/DC	Timber Mat	Y	Y	Y
27.6	sasv017e	30	Epheermal	UNT of Scott Taylor Creek	Ashland	Natural	N/A	2	5	Construction ROW			Mar 1 - Jun 15	46.36053282	-90.59715004	OC/DC	Timber Mat	Y	Y	Y
27.8	sasv018i	30	Intermittent	UNT of Scott Taylor Creek	Ashland	Manipulated	1	1	10	Construction ROW			Mar 1 - Jun 15	46.36240789	-90.5954587	OC/DC	Timber Mat	Y	Y	Y
27.9	sasv007e_x1	30	Epheermal	UNT of Gethman Creek	Ashland	Artificial/Man-made	2	1	2	Construction ROW			Mar 1 - Jun 15	46.36376557	-90.59440766	OC/DC	Timber Mat	Y	Y	Y
27.9	sasv007e_x2	30	Epheermal	UNT of Gethman Creek	Ashland	Artificial/Man-made	N/A	1	2	Access Road 066			Mar 1 - Jun 15	46.36379964	-90.59347776	N/A	Timber Mat	Y	N	Y
28.1	sas009e	30.31	Epheermal	UNT of Gethman Creek	Ashland	Artificial/Man-made	1	1	2	Construction ROW			Mar 1 - Jun 15	46.36151466	-90.59133551	OC/DC	Timber Mat	Y	Y	Y
28.1	sas005e	30.31	Epheermal	UNT of Gethman Creek	Ashland	Artificial/Man-made	1	1	2	Construction ROW			Mar 1 - Jun 15	46.36151615	-90.59115203	OC/DC	Timber Mat	Y	Y	Y
28.2	sas009p	30.31	Perennial	UNT of Gethman Creek	Ashland	Natural	8	8	10	Construction ROW		<i>perennial tributary of trout stream</i>	Sep 15 - May 15	46.365935	-90.58817056	DC	Timber Mat	Y	Y	Y
28.3	sasd017e	30	Epheermal	UNT of Gethman Creek	Ashland	Manipulated	N/A	2	4	Access Road 068			Mar 1 - Jun 15	46.36365862	-90.58619951	N/A	Timber Mat	Y	N	Y
28.4	sasd018e	30	Epheermal	UNT of Gethman Creek	Ashland	Manipulated	N/A	2	2	Access Road 068			Mar 1 - Jun 15	46.36404857	-90.58433607	N/A	Timber Mat	Y	N	Y
28.5	sasv011i_x1	31	Intermittent	UNT of Gethman Creek	Ashland	Natural	N/A	4	6	Access Road 069			Mar 1 - Jun 15	46.36490891	-90.58360385	N/A	Timber Mat	Y	N	Y
28.5	sasv011i_x2	31	Intermittent	UNT of Gethman Creek	Ashland	Natural	N/A	5	6	Access Road 069			Sep 15 - May 15	46.36654395	-90.58252938	OC/DC	Timber Mat	Y	N	Y
28.5	sasv010i	31	Epheermal	UNT of Gethman Creek	Ashland	Ditch	N/A	2	3	Access Road 069			Mar 1 - Jun 15	46.36815977	-90.58309054	N/A	Timber Mat	Y	N	Y
28.5	sasv008i_x1	31	Epheermal	Gethman Creek	Ashland	Natural	N/A	5	4	Access Road 069		Class II Trout, ASNRI-PNW	Sep 15 - May 15	46.36807754	-90.58235299	N/A	Timber Mat	Y	N	Y
28.6	sasv009i_x1	31	Epheermal	UNT of Gethman Creek	Ashland	Ditch	N/A	4	4	Access Road 069			Mar 1 - Jun 15	46.36807598	-90.58188045	N/A	Timber Mat	Y	N	Y
28.6	sasv007i	31	Epheermal	UNT of Gethman Creek	Ashland	Manipulated	N/A	2	2	Access Road 069			Mar 1 - Jun 15	46.3679994	-90.58146351	N/A	Timber Mat	Y	N	Y
28.6	sasv009i_x2	31	Epheermal	UNT of Gethman Creek	Ashland	Ditch	N/A	4	4	Access Road 069			Mar 1 - Jun 15	46.36804285	-90.58140443	N/A	Timber Mat	Y	N	Y
28.6	sasv008i_x2	31	Epheermal	Gethman Creek	Ashland	Natural	N/A	5	4	Access Road 069		Class II Trout, ASNRI-PNW	Sep 15 - May 15	46.36789974	-90.58050211	N/A	Timber Mat	Y	N	Y
29.6	sasv005i	32	Intermittent	Camp Four Creek	Ashland	Natural	7	6	12	Construction ROW		Class II Trout, ASNRI-PNW	Sep 15 - May 15	46.37582561	-90.56333852	OC/DC	Rail Car	Y	Y	Y
29.7	sasv006i	32	Epheermal	UNT of Camp Four Creek	Ashland	Natural	2	2	3	Construction ROW			Mar 1 - Jun 15	46.37625425	-90.56238879	OC/DC	Timber Mat	Y	Y	Y
29.7	sasv003i	32	Intermittent	Camp Four Creek	Ashland	Natural	N/A	4	4	Access Road 071		Class II Trout, ASNRI-PNW	Sep 15 - May 15	46.3777361	-90.56330902	N/A	Rail Car	Y	N	Y
29.8	WDH-31	34	Perennial	Unnamed Pond	Ashland	WDH Waterbody	N/A	N/A	N/A	East A Pipeyad			Mar 1 - Jun 15	46.39024469	-90.57320331	N/A	Timber Mat	Y	N	Y
30.5	sir0010p	32	Perennial	UNT of Feldcher Creek	Iron	Natural	6	5	10	Construction ROW		<i>perennial tributary of trout stream</i>	Sep 15 - May 15	46.3825256	-90.54804363	DC	Timber Mat	Y	Y	Y
30.7	sir0090e	32	Epheermal	UNT of Feldcher Creek	Iron	Manipulated	N/A	2	4	Access Road 073			Sep 15 - May 15	46.38446651	-90.54872462	N/A	Timber Mat	Y	N	Y
30.7	sir0090e_x2	32	Epheermal	UNT of Feldcher Creek	Iron	Artificial/Man-made	N/A	2	3	Construction ROW			Mar 1 - Jun 15	46.3848397	-90.54469152	OC/DC	Timber Mat	Y	Y	Y
30.8	sir0060e	33	Epheermal	UNT of Feldcher Creek	Iron	Manipulated	N/A	2	3	Access Road 074			Mar 1 - Jun 15	46.38602413	-90.54341677	N/A	Timber Mat	Y	N	Y
30.9	sir0007e	33	Epheermal	UNT of Feldcher Creek	Iron	Manipulated	N/A	1	2	Access Road 074			Mar 1 - Jun 15	46.38741195	-90.54025184	N/A	Timber Mat	Y	N	Y
31.6	WDH-103	36	Intermittent	Feldder Creek	Iron	WDH Waterbody	TBD	TBD	TBD	Construction ROW		Class II Trout, ASNRI-PNW	Sep 15 - May 15	46.39688201	-90.5429146	OC/DC	Timber Mat	Y	Y	Y
31.7	sas009i	35	Intermittent	UNT of Tyler Forks	Ashland	Natural	N/A	7	5	Access Road 082			Mar 1 - Jun 15	46.40732228	-90.53565231	N/A	Timber Mat	Y	N	Y
31.7	sir0090e	35	Intermittent	UNT of Tyler Forks	Ashland	Natural	N/A	3	10	Access Road 082			Mar 1 - Jun 15	46.4084724	-90.55113139	N/A	Timber Mat	Y	N	Y
31.8	sir008e_x1	35.36	Epheermal	Ditch	Iron	Artificial/Man-made	N/A	2	5	Access Road 076			Mar 1 - Jun 15	46.40135867	-90.54545009	N/A	Timber Mat	Y	N	Y
31.8	sir008e_x2	35.36	Epheermal	Ditch	Iron	Artificial/Man-made	N/A	2	5	Access Road 076			Mar 1 - Jun 15	46.40322998	-90.54524651	N/A	Timber Mat	Y	N	Y
31.8	sir006e_x1	35.36	Epheermal	Ditch	Iron	Artificial/Man-made	N/A	2	5	Access Road 076			Mar 1 - Jun 15	46.40336603	-90.54526949	N/A	Timber Mat	Y	N	Y
31.8	sir006e_x2	35.36	Epheermal	Ditch	Iron	Artificial/Man-made	N/A	2	5	Access Road 076			Mar 1 - Jun 15	46.4034525	-90.5450995	N/A	Timber Mat	Y	N	Y
31.8	sir007e	35.36	Epheermal	Ditch	Iron	Artificial/Man-made	N/A	1	5	Access Road 076			Mar 1 - Jun 15	46.40351721	-90.54513063	N/A	Timber Mat	Y	N	Y
31.9	sir002e_x1	35.36	Epheermal	Ditch	Iron	Artificial/Man-made	N/A	2	4	Access Road 076			Mar 1 - Jun 15	46.40363203	-90.54484683	N/A	Timber Mat	Y	N	Y
31.9	sir002e_x2	35.36	Epheermal	Ditch	Iron	Artificial/Man-made	N/A	2	4	Access Road 076			Mar 1 - Jun 15	46.40382604	-90.54467499	N/A	Timber Mat	Y	N	Y
32.0	sir001i	35.36	Intermittent	UNT of Tyler Forks	Iron	Natural	N/A	3	3	Access Road 076			Mar 1 - Jun 15	46.40480681	-90.5433836	N/A	Timber Mat	Y	N	Y
32.1	WDH-104	36	Intermittent	Feldder Creek	Iron	WDH Waterbody	TBD	TBD	TBD	Construction ROW		Class II Trout, ASNRI-PNW	Sep 15 - May 15	46.39688043	-90.52879802	Yes	Timber Mat	Y	N	Y
32.3	sir001e_x1	36	Epheermal	UNT of Feldcher Creek	Iron	Natural	N/A	7	13	Access Road 077			Mar 1 - Jun 15	46.4036882	-90.53120595	N/A	Timber Mat	Y	N	Y
32.4	WDH-32	36	Perennial	Unnamed Pond	Iron	WDH Waterbody	N/A	N/A	N/A	Access Road 080			Mar 1 - Jun 15	46.40548895	-90.5280071	N/A	Timber Mat	Y	N	Y
32.5	sir010e_x2	36	Epheermal	UNT of Feldcher Creek	Iron	Natural	N/A	7	13	Access Road 077			Mar 1 - Jun 15	46.40698165	-90.531171	N/A	Timber Mat	Y	N	Y
33.3	sir004p	37	Perennial	Tyler Forks	Iron	Natural	N/A	25	30	Access Road RSV5	ORW	Class II Trout, ASNRI-PNW	Sep 15 - May 15	46.41340312	-90.51677017	N/A	Rail Car	Y	N	Y
33.3	sir005i	37	Intermittent	UNT of Tyler Forks	Iron	Manipulated	N/A	4	6	Access Road RSV5			Mar 1 - Jun 15	46.41348157	-90.51597994	N/A	Timber Mat	Y	N	Y
33.3	sir006i_x1	37	Intermittent	UNT of Tyler Forks	Iron	Artificial/Man-made	N/A	4	6	Access Road RSV5			Mar 1 - Jun 15	46.41349334	-90.51512065	N/A	Timber Mat	Y	N	Y
33.3	sir006i_x2	37	Intermittent	UNT of Tyler Forks	Iron	Artificial/Man-made	N/A	4	6	Access Road RSV5			Mar 1 - Jun 15	46.41353525	-90.51391512	N/A	Timber Mat	Y	N	Y
33.4	sir007i	38	Intermittent	UNT of Tyler Forks	Iron	Artificial/Man-made	N/A	7	10	Access Road RSV5			Mar 1 - Jun 15	46.41406492	-90.51108481	N/A	Timber Mat	Y	N	Y
33.9	sir0002p	38	Perennial	Tyler Forks	Iron	Natural	58	50	60	Construction ROW	ORW	Class II Trout, ASNRI-PNW	Sep 15 - May 15	46.42314979	-90.51634539	DC	Rail Car	Y	Y	Y
33.9	sir005e	38	Epheermal	UNT of Tyler Forks	Iron	Natural	6	6	15	Construction ROW			Mar 1 - Jun 15	46.42365889	-90.51601692	OC/DC	Timber Mat	Y	Y	Y
33.9	sir008p	38	Perennial	Vogue Creek	Iron	Manipulated	N/A	6	8	Access Road 085		Class II Trout, ASNRI-PNW	Sep 15 - May 15	46.41898489	-90.5014765	N/A	Timber Mat	Y	N	Y
34.1	sir002p	38	Perennial	Vogue Creek	Iron	Natural	N/A	10	20	Access Road 084		Class II Trout, ASNRI-PNW	Sep 15 - May 15	46.42101923	-90.50436248	N/A	Timber Mat	Y	N	Y
34.3	WDH-105	38.40	Perennial	Vogue Creek	Iron	WDH Waterbody	N/A	TBD	TBD	Access Road 084		Class II Trout, ASNRI-PNW	Sep 15 - May 15	46.42374934	-90.50453875	Yes	Timber Mat	Y	N	Y
34.8	sir007e	38.40	Epheermal	Ditch	Iron	Manipulated	N/A	6	6	Access Road 085			Mar 1 - Jun 15	46.42435761	-90.49797942	N/A	Timber Mat	Y	N	Y
35.1	sir001e_x1	40	Epheermal	Ditch	Iron	Artificial/Man-made	N/A	1	5	Access Road 085			Mar 1 - Jun 15	46.43490311	-90.498852	N/A	Timber Mat	Y	N	Y
35																				

¹ OC: Open trench method used in conditions of no flow, sometimes referred to as the "Wet Trench" method.

DC: Open trench method used in conditions where a discernible water flow is present in the waterbody; referred to as the "Dry Crossing" method, where the construction zone is isolated and either a dam and pump or a flume pipe routes water around the excavation area.

HDD: Horizontal Directional Drill method used to install the pipeline using a trenchless technique. Crossings proposed as HDD will require temporary installation of tracking cables across waterbodies.

² Span Bridge: Timber Mat or Rail Car. All bridges may require in-stream support.

³ In addition to bridging, Enbridge proposed to allow clearing equipment and equipment necessary for installation of temporary equipment bridges, a single pass across waterbodies prior to bridge installation, unless restricted by applicable permits.

⁴ Enbridge has not yet completed surveys at this site to verify the location of the waterbody. Should the waterbody be within the proposed valve site footprint, Enbridge will either modify the valve site footprint to avoid the waterbody or modify the location of the valve site.

N/A = Not Applicable